

ACCOUNT & REFERENCE NUMBERS
RH: 01-863800 LH: 01-863818

MATERIAL INCLUDED IN ACCOUNT & REFERENCE FOR TURNOUT
(FURNISHED BY MANUFACTURER)

NO.	Item to be Opposite for LH TO DESCRIPTION RH as Shown.	ACC'T & REF.
2	27'-0" Switch Points, Double Reinforcing, IRH Str., ILH Str.	Note 11
2	Heel Block Assemblies, Attached to Switch Point	01-129103
2	39'-0" Undercut Stock Rail (IRH Bent; ILH Straight)	Note 15
1ea	No. 1 W/Basket, No. 2, No. 3 Ins. Vertical Switch Rods	Note 12
12	Adjustable Rail Brace CR Plan 73515-()	01-250354
1	No. 1-G Insulated Gage Plate CR Plan 73519-()	01-504008
2	No. 0 Adjustable Brace Slide Plate CR Plan 73519-()	01-526001
2	No. 1-A Adjustable Brace Slide Plate CR Plan 73519-()	01-526027
6	No. 1 Adjustable Brace Slide Plate CR Plan 73513-()	01-526019
12	No. 1-P Shoulder Slide Plate CR Plan 73513-()	01-526035
2ea.	Turnout Plates 8-2 thru 8-9 CR Plan 72220-() (I-Set)	01-540767
2	39'-0" Rail	—
1ea.	34'-0", 21'-0", 18'-0", 25'-6" Rail	—
1	No. 8 RBM Frog CR Plan 74160-()	01-332673
2	9'-0" Hook Flange Guard Rail CR Plan 71810-()	01-552452
714	5/8" x 6" AREA Spikes	01-781428
48	Cone Neck Drive Spikes 3/4" x 6"	01-754009
228	Rail Anchors	01-017704
112	Tie Plates CR Plan 72022-()	01-534302
14	FT 27	01-489200
2	FTR 29	01-489366
2	FT 27 Mod.	01-489408
2ea.	FTR 31 Mod., FTR 33 Mod.	01-489440, 01-489184
2ea.	FT 33, FT 33 Mod.	01-489242, 01-489465

NOTES

- All rails to be fully Heat Treated including Bonded Joint rails and frogging and heel rails.
- Switch rails to be samson.
- 39'-0" stock rails to be undercut as per Plan 73167-().
- For switch details see Plan 73180-().
- Gage plate No. 1-G as per Plan 73519-().
- Switch plates Nos. 0, 1, IA and IP as per Plan 73519-().
- Turnout plates No. 8-2 thru 8-9 as per Plan 72220-().
- Vertical insulated switch rods and adjustable rocker clips, generally as per Plan 73518-().
- Floating heel block as per Plan 73180-().
- All rails, including switch rails, to be drilled per Conrail Plan 71015-() for 132 RE rail, except that first hole is not to be drilled by the manufacturer. Conrail forces to field drill first hole where necessary.
- 27'-0" (16'-6" Str. Alinement) Account and Reference Numbers: RH Str. 01-653383 LH Str. 01-653391 CR Plan 73180-().
- Vertical Switch Rods (16'-6" Str. Alinement) Acc't & Ref. Nos. No. 1 Rod W/Basket 01-710761 No. 2 & No. 3 Rods 01-710779 CR Plan 73518-().
- Bonded Insulated Joint CR Plan 71370-(). Acc't & Ref. 01-454774. Furnished by Conrail.
- Frog Tie Plates as per Conrail Plan 72105-().
- 60'-0" Undercut Stock Rail Account and Reference Number (No Hand) 08-455501. To be ordered as a replacement as per CR Plan 73062-().

TIMBER SHIPPED WITH TURNOUT

QUANTITY	LENGTH
15	9'-0"
8	10'-0"
7	11'-0"
6	12'-0"
6	13'-0"
6	14'-0"
4	15'-0"
5	16'-0"
57	Total

LEGEND



- Indicates rails furnished by the manufacturer.
- - - Indicates rails furnished by Conrail.
- + Indicates standard bolted joint with 1/8" opening.
- ⊕ Indicates Bonded Insulated Joint. See Note 13
- ⊞ Indicates field welded joints.

CONRAIL 73206-A

STANDARD

No. 8 PANELED WELDED TURNOUT TIE AND RAIL LAYOUT-132 R.E.

MARCH, 1986



 Chief Engineer - Maintenance of Way Chief Engineering Officer