

ACCOUNT & REFERENCE NUMBERS  
RH: 01-863826 LH: 01-863834

**MATERIAL INCLUDED IN ACCOUNT & REFERENCE FOR TURNOUT**  
(FURNISHED BY MANUFACTURER)

| NO. | Item to be Opposite for LH TO DESCRIPTION RH as Shown.       | ACC'T & REF.         |
|-----|--|----------------------|
| 2   | 27'-0" Switch Points, Double Reinforcing, 1RH Str., 1LH Str. | Note 11              |
| 2   | Heel Block Assemblies, Attached to Switch Point              | 01-129103            |
| 2   | 39'-0" Undercut Stock Rail (1RH Bent; 1LH Straight)          | Note 15              |
| 1ea | No. 1 W/Basket, No. 2, No. 3 Ins. Vertical Switch Rods       | Note 12              |
| 12  | Adjustable Rail Brace CR Plan 73515-()                       | 01-250354            |
| 1   | No. 1-G Insulated Gage Plate CR Plan 73519-()                | 01-504008            |
| 2   | No. 0 Adjustable Brace Slide Plate CR Plan 73519-()          | 01-526001            |
| 2   | No. 1-A Adjustable Brace Slide Plate CR Plan 73519-()        | 01-526027            |
| 6   | No. 1 Adjustable Brace Slide Plate CR Plan 73513-()          | 01-526019            |
| 12  | No. 1-P Shoulder Slide Plate CR Plan 73513-()                | 01-526035            |
| 2ea | Turnout Plates 8-2 thru 8-11 CR Plan 72220-() (1-Set)        | 01-540767            |
| 2   | 39'-0" Rail  | —                    |
| 1ea | 34'-0", 21'-0", 18'-0", 25'-6" Rail                          | —                    |
| 1   | No. 8 RBM Frog CR Plan 74160-()                              | 01-332673            |
| 2   | 9'-0" Hook Flange Guard Rail CR Plan 71810-()                | 01-552452            |
| 714 | 5/8 x 6" AREA Spikes   | 01-781428            |
| 48  | Cone Neck Drive Spikes 3/4 x 6"                              | 01-754009            |
| 228 | Rail Anchors   | 01-017704            |
| 112 | Tie Plates CR Plan 72022-()                                  | 01-534302            |
| 14  | FT 27  | 01-489200            |
| 2   | FTR 29   | 01-489366            |
| 2   | FT 27 Mod.   | 01-489408            |
| 2ea | FTR 31 Mod., FTR 33 Mod.                                     | 01-489440, 01-489184 |
| 2ea | FT 33, FT 33 Mod.  | 01-489242, 01-489465 |

**NOTES**


- All rails to be fully Heat Treated including Bonded Joint rails and frog wing and heel rails.
- Switch rails to be samson.
- 39'-0" stock rails to be undercut as per Plan 73167-().
- For switch details see Plan 73180-().
- Gage plate No. 1-G as per Plan 73519-().
- Switch plates Nos. 0, 1, 1A and 1P as per Plan 73519-().
- Turnout plates No. 8-2 thru 8-11 as per Plan 72220-().
- Vertical insulated switch rods and adjustable rocker clips, generally as per Plan 73518-().
- Floating heel block as per Plan 73180-().
- All rails, including switch rails, to be drilled per Conrail Plan 71015-() for 132 RE rail, except that first hole is not to be drilled by the manufacturer. Conrail forces to field drill first hole where necessary.
- 27'-0" (16'-6" Str. Alignment) Account and Reference Numbers:  
RH Str. 01-653383 LH Str. 01-653391 CR Plan 73180-().
- Vertical Switch Rods (16'-6" Str. Alignment) Acc't & Ref. Nos.  
No. 1 Rod W/Basket 01-710761 No. 2 Rod 01-710779  
No. 3 Rod 01-710803 CR Plan 73518-().
- Bonded Insulated Joint  
Furnished by Conrail.
- Frog Tie Plates as per Conrail Plan 72105-().
- 60'-0" Undercut Stock Rail Account and Reference Number (No Hand)  
08-455501. To be ordered as a replacement as per CR Plan 73062-().
- HP Plates under Heel Block are the same as 1P Plates except 24" long.

**TIMBER SHIPPED WITH TURNOUT**

| QUANTITY | LENGTH |
|----------|--------|
| 15       | 9'-0"  |
| 8        | 10'-0" |
| 7        | 11'-0" |
| 6        | 12'-0" |
| 6        | 13'-0" |
| 6        | 14'-0" |
| 4        | 15'-0" |
| 5        | 16'-0" |
| 57       | Total  |

**LEGEND**

- Indicates rails furnished by the manufacturer.
- - - Indicates rails furnished by Conrail.
- + Indicates standard bolted joint with 1/8" opening.
- ⊕ Indicates Bonded Insulated Joint.
- ⊞ Indicates field welded joints.



**CONRAIL** 73206-B  
STANDARD

**No. 8 paneled welded turnout tie and rail layout-132 R.E.**  
MARCH, 1986

*J. R. Clark*  
Chief Engineer - Maintenance of Way

*W. B. Gordon*  
Chief Engineering Officer