



ACCOUNT & REFERENCE NUMBERS
RH: 01-863867 LH: 01-863875

MATERIAL INCLUDED IN ACCOUNT & REFERENCE FOR TURNOUT
(FURNISHED BY MANUFACTURER)

NO.	Item to be Opposite for LH TO DESCRIPTION RH as Shown.	ACC'T & REF.
2	27'-0" Switch Points, Double Reinforcing, 1 RH Str., 1 LH Str.	Note 11
2	Heel Block Assemblies, Attached to Switch Point	01-129103
2	39'-0" Undercut Stock Rail (1 RH Bent; 1 LH Straight)	Note 15
1 ea.	No. 1 W/Basket, No. 2, No. 3 Ins. Vertical Switch Rods	Note 12
12	Adjustable Rail Brace CR Plan 73515-()	01-250354
1	No. 1-G Insulated Gage Plate CR Plan 73519-()	01-504008
2	No. 0 Adjustable Brace Slide Plate CR Plan 73519-()	01-526001
2	No. 1-A Adjustable Brace Slide Plate CR Plan 73519-()	01-526027
6	No. 1 Adjustable Brace Slide Plate CR Plan 73513-()	01-526019
12	No. 1-P Shoulder Slide Plate CR Plan 73513-()	01-526035
2 ea.	Turnout Plates 10-2 thru 10-11 CR Plan 72220-() (1-Set)	01-540882
2	39'-0" Rail	—
1 ea.	35'-8", 21'-0", 18'-0", 40'-10 3/4" Rail	—
1	No. 10 RBM Frog CR Plan 74161-()	01-332806
2	9'-0" Hook Flange-Guard Rail CR Plan 71810-()	01-552452
841	5/8" x 6" AREA Spikes	01-781428
48	Cone Neck Drive Spikes 3/4" x 6"	01-754009
256	Rail Anchors	01-017704
144	Tie Plates CR Plan 72022-()	01-534302
4	FT 20	01-489218
6	FT 23	01-489226
10	FT 27	01-489200
2 ea.	FT 29, FTR 29, FT 27 Mod. 01-489127, 01-489366, 01-489408	
2 ea.	FT 29 Mod., FTR 31 Mod., FTR 33 Mod. 01-489473, 01-489440, 01-489184	

NOTES

- All rails to be fully Heat Treated including Bonded Joint rails and frog wing and heel rails.
- Switch rails to be samson.
- 39'-0" stock rails to be undercut as per Plan 73167-().
- For switch details see Plan 73181-().
- Gage plate No. 1-G as per Plan 73519-().
- Switch plates Nos. 0, 1, IA and IP as per Plan 73519-().
- Turnout plates No. 10-2 thru 10-11 as per Plan 72220-().
- Vertical insulated switch rods and adjustable rocker clips, generally as per Plan 73518-().
- Floating heel block as per Plan 73181-().
- All rails, including switch rails, to be drilled per Conrail Plan 71015-() for 132 RE rail, except that first hole is not to be drilled by the manufacturer. Conrail forces to field drill first hole where necessary.
- 27'-0" (16'-6" Str. Alinement) Account and Reference Numbers: RH Str. 01-653383 LH Str. 01-653391 CR Plan 73181-().
- Vertical Switch Rods (16'-6" Str. Alinement) Acc't & Ref. Nos. No. 1 Rod W/Basket 01-710761 No. 2 Rod 01-710779 No. 3 Rod 01-710803 CR Plan 73518-().
- Bonded Insulated Joint
Furnished by Conrail.
- Frog Tie Plates as per Conrail Plan 72105-().
- 60'-0" Undercut Stock Rail Account and Reference Number (No Hand) 08-455501. To be ordered as a replacement as per CR Plan 73062-().
- HP Plates under Heel Block are the same as IP Plates except 24" long.

TIMBER SHIPPED WITH TURNOUT

QUANTITY	LENGTH
15	9'-0"
11	10'-0"
9	11'-0"
5	12'-0"
8	13'-0"
6	14'-0"
6	15'-0"
7	16'-0"
67	Total

LEGEND

- Indicates rails furnished by the manufacturer.
- - - Indicates rails furnished by Conrail.
- + Indicates standard bolted joint with 1/8" opening.
- ⊕ Indicates Bonded Insulated Joint.
- ⊞ Indicates field welded joints.



CONRAIL 73207-B
STANDARD

No. 10 PANELED WELDED TURNOUT TIE AND RAIL LAYOUT-132 R.E.
MARCH, 1986

J. R. Clark
Chief Engineer - Maintenance of Way

J. E. Gordon
Chief Engineering Officer